

INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)
Transit Campus: C/o. Sree Rama Engineering College, Karakambadi Road,
Mangalam (P.O.), Tirupati, Andhra Pradesh – 517 507.

NIQ No: 11/IISER/Tirupati/NIQ/2022-2023

Date: 22.02.2023

NOTICE INVITING QUOTATION

Item rate sealed quotation are invited by the undersigned on behalf of Director IISER Tirupati for the following work.

SI. No	Name of Work	Time Period of Contract	Start Date of Bid	End Date & time of Bid	Opening Date & time of Bid
1	Construction of a Practice cricket pitch, Basketball court painting and miscellaneous works at IISER Tirupati Permanent campus, Yerpedu.	14 Days	22.02.2023	28.02.2023 at 03:00 p.m.	28.02.2023 at 03:30 p.m.

TERMS AND CONDITIONS

- 1) No advance payment shall be made by IISER Tirupati.
- 2) Applicants quoting for this work should be a registered "Civil Contractor" in CPWD/ AP state PWD/ MES/ Railways/ Autonomous bodies, or should have executed similar civil works in any of the government organizations. The proof of a similar work experience should be submitted along with the quotation. Agency must visit the site before quoting the NIQ for better understanding.
- 3) Time period for completion of work shall be 14 Days from the date of placing the confirmed order by IISER Tirupati. The act of backing-out after quotation will debar such agencies for participating in future quotations of IISER Tirupati. Bidder may e-mail queries on engineering@iisertirupati.ac.in or submit to the IISER Tirupati office in hard copy on all working days before a day of the submission date of quotation.
- 4) All agencies need to submit their quotation in hard copy in a sealed envelope at IISER Tirupati, Transit Campus by suitable means on and before 3 PM on 28/02/2023. The quotation received after the date & time specified above shall not be accepted. Any delays, postal delays, etc. will not be entertained. Agency should quote for all the items in the BOQ. The bid shall be submitted in the original bid document (as issued by the IISER Tirupati) superscribing the name of work. Quotations will be opened on the same day i.e., 28/02/2023 at 3.30 PM in the presence of bidder or their authorized representatives if any. The offer of the firm should be commercially clear including acceptance of all terms and conditions without assigning any reasons.
- 5) Quoted rates should be inclusive of the cost of all the materials, labour cost, octroi, duties, cost of sample, and fees towards testing of materials in labs, royalties, GST, etc. Nothing extra shall be paid.



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)
Transit Campus: C/o. Sree Rama Engineering College, Karakambadi Road,
Mangalam (P.O.), Tirupati, Andhra Pradesh – 517 507.

- 6) All approved makes shall be as specified in BOQ and as per CPWD specifications, the agency should put-up technical data and obtain prior approval on makes of various materials of IISER Tirupati before taking-up work.
- 7) The successful agency shall make its arrangement for all Tools & tackles for work etc. complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location.
- 8) TDS and other applicable taxes and cess will be deducted from the bills as of the work.
- 9) Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER Tirupati wherever CPWD/ IS specification are not available.
- 10) The contractor shall ensure that minimum wages should be paid to the labour's and employees in accordance with labour laws.
- 11) Agency to submit computerized measurement and abstract sheets to IISER Tirupati for payments.
- 12) Amount quoted for items should be as specified in the BOQ.
- 13) Following the latest developments and restrictions imposed in the country and state in view of the COVID-19, successful agency should ensure all safety precautions, social distancing norms during the execution of work.

Executive Engineer, HSER Tirupati On behalf of Director HSER, Tirupati

Copy to:

- 1. The Registrar, IISER Tirupati.
- 2. Deputy Registrar F & A.
- 3. Assistant Engineer Civil.



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)
Transit Campus: C/o. Sree Rama Engineering College, Karakambadi Road,
Mangalam (P.O.), Tirupati, Andhra Pradesh – 517 507.

SCHEDULE OF QUANTITIES

Name of Work: Construction of a Practice cricket pitch, Basketball court painting and miscellaneous works at IISER Tirupati Permanent campus, Yerpedu.

S No.	Description of Item	UNIT	QTY	RATE in Rs	AMOUNT in Rs
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m	Cum	26		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m	Cum	18		
3	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	402		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	kg	160		
5	Providing and laying design mix cement concrete of M-30 grade, using cement content as per design mix, using coarse sand and graded stone aggregate of 20 mm nominal size in appropriate proportions as per approved & with screed board vibrator, needle vibrator, vacuum dewatering process and finally finished by floating, brooming etc. including M S channel side	EDIO E			

Vhazerjan

Page 3 of 5



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)
Transit Campus: C/o. Sree Rama Engineering College, Karakambadi Road,
Mangalam (P.O.), Tirupati, Andhra Pradesh – 517 507.

	shuttering laid in required line and level/grade including cutting contraction joints grooves at interval not exceeding 3m in both directions, expansion for contraction, construction & longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete joints at required intervals, filling all the joints with "A" Grade sealing compound complete as per CPWD specifications and direction of Engineer in charge. (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately). Note: - Cement content considered in M-30 is @ 340 kg/cum. Excess/less cement used as per design mix is payable/ recoverable separately.			
	Cement concrete manufactured in automatic batching plant (RMC plant) i/c transportation to site in transit mixer	Cum	5	
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size de rived from natural sources)	Cum	4	
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	Sqm	15	
8	Finishing with Sandex mat floor paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete on concrete floor	Sqm	560	
9	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	sqm	550	

V Lune Gim



INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH TIRUPATI

(An Autonomous Institution of Ministry of Education, Govt. of India)
Transit Campus: C/o. Sree Rama Engineering College, Karakambadi Road,
Mangalam (P.O.), Tirupati, Andhra Pradesh – 517 507.

Total Amount in Words:			

Note: -

• Amount quoted above shall be inclusive of GST, transportation, statutory, labour fees etc. nothing extra shall be payable.

Vhancijan 21/1/23

Executive Engineer, IISER Tirupati On behalf of Director IISER, Tirupati

(To be filled by the Agency)

Signature of the bidder

:

Name of the Agency

.

Mobile Number & E-mail ID

÷

Correspondence Address

: